



1. All work shall conform to the Elsinore Valley Municipal Water District (EVMWD) design and construction standards for water, recycled water and sanitary sewer facilities.
2. Construction materials testing and inspection shall comply with standards and specifications and shall meet or exceed the requirements of the governing agency, the Standard Specifications for Public Works Construction ("Green Book") and the American Society for Testing and Materials (ASTM) standards. Failure to meet any of the above requirements shall be cause for rejection.
3. The contractor shall notify EVMWD (5) five working days prior to beginning work (951) 674-3146.
4. Depth and location of existing underground facilities shall be determined by the contractor by potholing and a field survey of elevations and shall be given to the inspector prior to trenching. The contractor shall also contact Underground Service Alert (811) prior to any excavation work.
5. All construction and operations by the contractor shall be in accordance with Cal-OSHA requirements.
6. The contractor shall keep a complete record of all construction changes and shall make information available to the inspector for preparation of "As Built" drawings. The "As Built" drawings shall be submitted to EVMWD for review prior to final review and acceptance of the project.
7. Where the water main and sewer cross storm drains, other pipelines, telephone and electric ducts, or similar installations, a minimum of 12 inches of vertical clearance shall be provided between the main or sewer and other installations unless otherwise directed by EVMWD personnel.
8. Separation of sewer and water lines must comply with EVMWD standard plans S-3 or W-2 and shall meet or exceed the requirements of the State of California, Department of Public Health Title 22, Chapter 16, Article 4, Section 64572.
9. Connections to existing EVMWD sewer or water lines shall be in accordance with standard EVMWD procedures and shall not be made unless EVMWD inspector is present.
10. Unless waived by EVMWD an insulated copper solid core 10 gage tracer wire shall be placed with each sewer main to assist with future location. Warning tape shall be placed at least 6" above sewer main & sewer laterals, but not deeper than 24" below the existing finished grade. Water mains shall also have tracer wire and warning tape installed in the trench.

REVISION	BY	APPR	DATE	 ELSINORE VALLEY MUNICIPAL WATER DISTRICT	GENERAL NOTES	STD. DWG. NO.
						 06/22/2023 PARAG KALARIA R.C.E. 83927 DATE