

NOTES:

- 1. ALL DOMESTIC BACKFLOW AND PLUMBING SHALL BE LEAD-FREE.
- 2. LOCATE THE ASSEMBLY A MINIMUM 1' PAST THE METER BOX. OTHER LOCATIONS MUST BE APPROVED BY THE DISTRICT INSPECTOR PRIOR TO INSTALLATION.
- 3. THE BACKFLOW PREVENTER ASSEMBLY SHALL CONSIST OF AN APPROVED REDUCED PRESSURE OR DOUBLE DETECTOR CHECK VALVE IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS. THE ASSEMBLIES SHALL BE SUITABLE FOR SUPPLY PRESSURES.
- 4. THE BACKFLOW ASSEMBLY SHALL BE OF BRONZE CONSTRUCTION WITH ALL CONNECTIONS ON THE UNIT TO BE THREADED BRASS OR SWEATED COPPER MATERIAL FOR 3/4" THROUGH 2"; 2 1/2" AND ABOVE SHALL HAVE FLANGED FITTINGS TOGETHER WITH STAINLESS STEEL NUTS AND BOLTS.
- 5. LOCATION AND INSTALLATION SHALL BE PER PLAN AS SUBMITTED TO AND ACCEPTED BY THE DISTRICT.
- 6. ALL ASSEMBLIES 2 1/2" AND LARGER TO BE INSTALLED SHALL BE EQUIPPED WITH RESILIENT WEDGE GATE VALVES.
- 7. CLEARANCES ARE SHOWN, EXCEPT THAT LATERAL CLEARANCES SHALL BE 12-INCHES MINIMUM EACH DIRECTION.
- 8. ASSEMBLIES SHALL NOT BE LOCATED IN AREAS SUBJECT TO FLOODING.
- 9. ONLY SECURITY ENCLOSURES PROVIDING ADEQUATE CLEARANCES AND FULL VIEW OF ASSEMBLY SHALL BE PERMITTED.
- 10. LANDSCAPING OR CONSTRUCTION AROUND ASSEMBLY SHALL PERMIT AN UNOBSTRUCTED VIEW FROM AT LEAST ONE PUBLIC VANTAGE POINT.
- 11. FINAL INSPECTION AND ACCEPTANCE TEST SHALL BE PROVIDED BY DISTRICT BACKFLOW INSPECTOR.
- 12. NO CONNECTIONS OR TEES ARE PERMITTED BETWEEN METER AND BACKFLOW PREVENTER.
- 13. SIZES 3" AND LARGER SHALL HAVE ADDITIONAL PIPE SUPPORT.
- 14. SIZES 3/4" THROUGH 2" SHALL HAVE (1) UNION PLACED ON DOWNSTREAM CUSTOMER PIPING.
- 15. BACKFLOW ASSEMBLY TO BE THE SAME SIZE OR ONE SIZE LARGER THAN METER.
- 16. MATERIALS SHALL BE SELECTED FROM THE APPROVED MATERIALS LIST.
- 17. BRASS PLUGS ARE TO BE USED.
- 18. CONCRETE SHALL HAVE #4 @ 12" OC EW MIN. CONCRETE SHALL BE CLASS 560-C-3250.

ITEM	DESCRIPTION						
1	ACCEPTED BACKFLOW PREVENTION ASSEMBLY						
2	BALL VALVE (CUSTOMER SERVICE VALVE)						
3	SERVICE METER						
4	WATER MAIN						
	SION	BY	APPR	DATE	÷		STD. DWG. NO.
REV 1	REV 1 MO				煮 ELSINORE	BACKFLOW PREVENTION	
						ASSEMBLY ABOVE GROUND	W-21A
					MUNICIPAL WATER DISTRICT		
					Pobalaan - 06/22/2023	INSTALLATION	
					PARAG KALARIA R.C.E. 83927 DATE	·····	